



**INTERNATIONAL
ASTRONAUTICAL
FEDERATION**

Update on Risk Reduction Activities for a Liquid Advanced Booster for NASA's Space Launch System

**Andy Crocker, Dynetics, Inc.
Bart Graham, Aerojet Rocketdyne**

67th International Astronautical Congress, Guadalajara, Mexico, Sept 26-30, 2016

Overview and Introduction to ABEDRR

- **Goals of NASA's Advanced Booster Engineering Demonstration and/or Risk Reduction (ABEDRR) are to:**
 - Reduce risks leading to an affordable Advanced Booster that meets the evolved capabilities of SLS
 - Enable competition by mitigating targeted Advanced Booster risks to enhance SLS affordability
- **SLS Block 1 vehicle is being designed to carry 70 mT to LEO**
 - Uses two five-segment solid rocket boosters (SRBs) similar to the boosters that helped power the space shuttle to orbit
- **Evolved 130 mT payload class rocket requires an advanced booster with more thrust than any existing U.S. liquid- or solid-fueled boosters**

Scope of This Presentation

- **In October 2012 and February 2013, NASA awarded a contract to Dynetics, Inc. (with Aerojet Rocketdyne as a major subcontractor):**
 - To demo the use of modern manufacturing techniques to produce and test several primary components of the F-1 rocket engine originally developed for the Apollo Program, including an integrated powerpack
 - To demo innovative fab techniques for metallic cryo tanks
- **Early 2014, NASA and Dynetics agreed to move additional large liquid oxygen/kerosene engine work under Dynetics**
 - Originally had been its own ABEDRR prime contract to Aerojet
- **Led by Aerojet Rocketdyne, work is focused on an Oxidizer-Rich Staged Combustion (ORSC) cycle engine**
 - Can apply to both NASA's Advanced Booster and other launch vehicle applications, including Atlas V booster engine
 - Effort will demonstrate combustion stability and performance of a full-scale ORSC cycle main injector and chamber
- **This presentation will discuss the Dynetics ABEDRR engine task (both efforts) and structures task achievements to date**



Dynetics Risk Reduction Task Summary



(A)



Engineering Demonstrations and Risk Reduction Tasks

Benefit of Proposed Effort/Status at Start of DDT&E

F-1B Engine Risk Reduction

Aerojet Rocketdyne Lead

- | | |
|--|--|
| • Gas Generator Build and Test | • Full-Scale, Low-Cost, Production-Like, Throttling GG Hot-Fired |
| • Turbopump Build | • Full-Scale, Low-Cost, Production-Like, Throttling TPA Built |
| • Powerpack Build and Test | • Full-Scale, Low-Cost, Production-Like, Throttling PPA Hot-Fired |
| • Thrust Chamber Assembly Design and Build | • Full-Scale, Low-Cost, Production-Like, HIP-Bonded TCA Demonstrated |

(B)



Structures Risk Reduction

Dynetics Lead

- | | |
|------------------------------------|---|
| • Cryotank Assembly Build | • Full-Scale 18-ft Diameter Flight-Like Tank and Intertank Verified |
| • Cryotank Proof and Thermal Cycle | • Full-Scale Design, Tooling, and Build Processes Verified |

(A)



ORSC Cycle Engine Risk Reduction

Aerojet Rocketdyne Lead

- | | |
|---|--|
| • Main Injector and Thrust Chamber Assembly Design, Build, and Test | • Full-Scale Demonstration of Combustion Stability and Performance Measurement |
|---|--|



Overall F-1B Engine Risk Reduction Summary


- **Program objective was to reduce F-1B engine development risks—despite funding challenges, the effort met this objective:**
 - Demonstrated F-1B engine and component understanding and readiness
 - Completed a heritage gas generator (GG) hot-fire test series, proving throttling capability
 - Completed an additively manufactured GG injector hot-fire test series, proving similarity to heritage
 - Disassembled and reverse engineered existing Mk-10A turbopump
 - Demonstrated long-term affordability through full-scale demonstrations of an additively manufactured GG injector and a cast LOX volute, turbine blades, and turbine manifold
 - Prepared main propellant valves for test
 - Integrated engine loads and design, developed transient operational models, and designed interfaces with the facility for Powerpack testing
 - Developed a new MCC design focused on dramatic cost reductions





Structures Risk Reduction – Cryotank Build

- Structures risk reduction task planned to validate the designs, materials, equipment, and processes to produce robust and affordable structures
- The task created a full-scale cryotank assembly that was verified by proof pressure and cryo-thermal cycle testing
- Original plan was to build a tank with four barrel sections, but NASA negotiated with Dynetics to reduce schedule and cost by building a tank with a single cylindrical barrel
 - Circumferential welding still demonstrated, and testing still completed





INTERNATIONAL
ASTRONAUTICAL
FEDERATION

Structures Risk Reduction – Testing

Cryothermal Cycle / Proof Test



Integrated test article chilled
with LN₂

Moments after tank burst


Burst Test






INTERNATIONAL
ASTRONAUTICAL
FEDERATION

Ox-Rich Staged Combustion (ORSC) Cycle Engine





NASA/USAF-Funded Integrated Ox-Rich Test Article




- Preburner testing at the 250 klbf thrust level. ORSC main injector combustion stability and injector performance results at 500 klbf thrust level. Direct design information and model validation data.



= Focus of this presentation



Test Configurations





Integrating Components (IC) Summary Status

- **Accomplishments**
 - Completed IC CDR in Aug 2015
 - Completed IC Delta CDR in Nov 2015
 - Completed pouring of all cast parts
 - Completed casting process on several key components
- **Status**
 - Drawing status: 74% released
 - All remaining major component machine drawings are in signature cycle
 - Machining of IC hardware on schedule to support testing
- **Upcoming Events**
 - Release remaining IC piece part drawings
 - Complete machining of IC hardware per schedule



Main Injector Summary Status

- **Accomplishments**

- Completed CDR in Mar 2016
- Completed Delta CDR in June 2016
- Ran hydraulic CFD to design flow distribution through manifold and injector elements
- Ran reacting-flow CFD in sub-models and full-sector models to determine driving temperatures at various power levels, engine conditions, cooling flows, etc.
- Resolved thermal compatibility issues to eliminate hot spots / streaks
- Performed acoustic analyses to find stable configurations and conditions
- Performed structural analysis to determine injector has positive margins and meets life requirements
- Finalized design of injector elements and injector assembly
 - Included stability aids (baffles and cavities) for improved high frequency stability margin
- Developed fabrication plan, and verified / updated with sub-scale injector Manufacturing Technology Demonstrators (MTDs)



Main Injector Summary Status (cont'd)

- **Status**
 - Completing cold flows to determine final propellant flow paths
 - ~80% of drawings released and out for procurement
 - Completed major injector forgings; moved to machining
 - Majority of injector components in fabrication



Chamber Summary Status

- **Accomplishments**

- Ran reacting-flow CFD in sub-models and full-sector models and thermal analysis to determine driving temperatures at various power levels, engine conditions, cooling flows, etc.
- Resolved thermal compatibility issues to eliminate hot spots / streaks
- Performed structural analysis to determine chamber has positive margins and meets life requirements
- Finalized cooling design with thermal/structural and flow requirements
- Finalized design of chamber
 - Finalized cooling approach
 - Modified features to reduce strain and improve low cycle fatigue
- Optimized geometry for manufacturability
- Baselined braze parameters; demonstrated braze parameters
- Defined and matured manufacturing processes




Chamber Summary Status (cont'd)

- **Status**
 - Drawings ~70% complete
 - Procurement on schedule
 - Machining of hardware on schedule to support testing
- **Upcoming Events**
 - Complete remaining braze trials
 - Release remaining piece part drawings
 - Complete machining of hardware per schedule




INTERNATIONAL
ASTRONAUTICAL
FEDERATION


Examples of Fluid, Thermal, Structural, and Acoustic Analyses




Analysis of coolant flow along chamber wall




Chamber wall temperature analyses using CFD



Stability analysis / acoustic modeling of injector and chamber



Reacting flow CFD of injector streamlines




Structural model of thrust chamber assembly



INTERNATIONAL
ASTRONAUTICAL
FEDERATION


Testing at NASA Stennis Space Center Stand E1





Test Skid Assembly Design Status

- Completed Conceptual Design Review in Oct 2015
- Completed Preliminary Design Review in Dec 2015
- Completed Detailed Design Review in Feb 2016





Test Skid Assembly Build Status

- **Thrust Takeout Structure**
 - Final welding complete; post-weld inspection complete
 - Thrust takeout plates in machining
 - Stress relief after welding
 - Then final machining and painting
- **Exhaust duct**
 - Final welding complete; post-weld inspection complete
 - Moved to large gantry mill for post-weld machining
 - Then proof testing and final processing
- **Carriage assembly**
 - Final weld complete; post-weld machining complete; inspection complete
 - Next step: painting
- **Platform**
 - Welding in work; will finish sometime next week
 - Next steps: NDT → paint
- **Build completion expected end of October**



INTERNATIONAL
ASTRONAUTICAL
FEDERATION

Test Skid Assembly Build Progress Thrust Takeout Structure (Post-Weld)





INTERNATIONAL
ASTRONAUTICAL
FEDERATION


Test Skid Assembly Build Progress (cont'd) Exhaust Duct (Post-Weld)





INTERNATIONAL
ASTRONAUTICAL
FEDERATION

Test Skid Assembly Build Progress (cont'd) Carriage Assembly (Post-Weld)





Summary

- **Dynetics has designed innovative structure assemblies; manufactured them using FSW to leverage NASA investments in tools, facilities, and processes; conducted proof and burst testing, demonstrating viability of design/build processes**
- **Dynetics/AR has applied state-of-the-art manufacturing and processing techniques to the heritage F-1, reducing risk for engine development**
- **Dynetics/AR has also made progress on technology demonstrations for ORSC cycle engine, which offers affordability and performance for both NASA and other launch vehicles**
 - Full-scale integrated oxidizer-rich test article
 - Testing will evaluate performance and combustion stability characteristics
 - Contributes to technology maturation for ox-rich staged combustion engines

